



---

## **Requirements for Submitting Swimming Pool Plans**

### **Gunite:**

1. Site plan (three (3) copies).
2. Site plans must specify how you will comply with the County of Nevada, Access Safety For Swimming Pools & Spas (LUDC 14.03..200), indicate location of pool equipment, show location of pool excavation spoils.
3. California Engineers wet stamped and signed reinforcing steel plan (two (2) copies, wet stamped/signed).
4. Highlight the steel schedule and other details that will apply to the project.
5. If a pool heater is installed, note on the plan that the heater will comply with the 2025 California Energy Code and the 2024 International Swimming Pool & Spa Code. Indicate location of pool equipment on site plan. Heated pools require a pool cover per the California Energy Code. Attach California Energy Code form CF2R-PLB-03 to the plans to be completed by the licensed contractor.
6. Complete and submit the swimming pool barrier form.

### **Vinyl Lined & Fiberglass:**

1. Site plan (three (3) copies).
2. Site plans must specify how you will comply with the County of Nevada, Access Safety For Swimming Pools & Spas (LUDC 14.03.200), show location of pool equipment, show location of pool excavation spoils.
3. Approval from ICC (International Code Council) Evaluation Service that the pool meets Building Code requirements two (2) copies **or**
4. California Engineers wet stamped and signed plans two (2) copies.
5. If a pool heater is installed, note on the plan that the heater will comply with the 2025 California Energy Code and the 20254International Swimming Pool & Spa Code. Indicate location of pool equipment on site plan. Heated pools require a pool cover per the California Energy Code. Attach California Energy Code form CF2R-PLB-03 to the plans to be completed by the licensed contractor.
6. Elevated deck(s) around pools require a permit. Submit deck plans and indicate the deck(s) on the site plan.
7. Complete and submit the swimming pool barrier form.

**(See back for inspection requirements)**

## **Swimming Pool Inspections**

### **In Ground Pools**

1. Pre-gunite inspection: When steel is in place and bonded, before any concrete is placed. Also all underground/under-slab utilities will be inspected; circulation lines and gas lines shall be on test for inspection.
2. Pre-deck inspection: All steel is bonded and the equipotential bonding grid is completed per the California Electrical Code.
3. Pre-plaster inspection: When gunite is in place, before the finish coat of plaster is applied. At this inspection, the swimming pool barrier shall be installed.
4. Final Inspection: The pool is completed and ready for use.

### **Above Ground Pools**

1. Rough electrical inspection. When pool is set-up, before electrical is hooked up and before pool is filled with water. At this inspection, the swimming pool barrier shall be installed.
2. Pre-deck inspection. (Before deck footings are poured and before pool is filled). Equipotential bonding grid may be required depending on pool construction material.
3. Final Inspection: The pool is completed and ready for use.

## **FENCING REQUIREMENTS FOR SWIMMING POOLS**

**See the Swimming Pool Barrier form for complete information**

.....