



COUNTY OF NEVADA
COMMUNITY DEVELOPMENT AGENCY

Sean Powers, Director

ENVIRONMENTAL HEALTH DEPARTMENT

Amy Irani, REHS, Director

950 MAIDU AVENUE
NEVADA CITY, CA 95959

PH: (530) 265-1222
FAX: (530) 265-9853

<http://mynevadacounty.com>

Septic As-Built Instructions :

As accurately as possible, show locations of the septic tank, leach field, cross-over pipes, clean-outs, pump tank, curtain drain, well (if applicable), and any other components of the system you installed. Reference the septic tank and the ends of all leach lines from two building foundation corners (preferred), or two other permanent objects. Give distance measurements: house to tank, tank to first leach line, all leach line ends to crossovers, leach line lengths, and lengths of crossovers between trenches. Show distance from the tank and leach field to the well (if applicable). Show repair area, and any additional measurements requested by the permit. Draw North Arrow. Use an attachment if needed.

The as-built drawing must be on site at the time of final inspection. If the as-built is not available, it may require a re-inspection and additional fee.

FIGURE 7 - SAMPLE SEPTIC AS-BUILTS

